

Mechanical properties	Value	Unit	Test Standard
Other Standards^[S]			
Tensile Strength	200	MPa	
Flexural modulus, 23°C	9500	MPa	

S: These properties are reported by the producer according standards that are different to our defaults.

Other properties	Value	Unit	Test Standard
Water absorption	3.5	%	Sim. to ISO 62
Other Standards^[S]			
Density	1430	kg/m ³	

S: These properties are reported by the producer according standards that are different to our defaults.

Processing Recommendation Injection Molding	Value	Unit	Test Standard
Pre-drying - Temperature	100 - 120	°C	-
Pre-drying - Time	2 - 4	h	-
Melt temperature	280 - 325	°C	-
Mold temperature	100 - 140	°C	-

Characteristics

Processing

Injection Molding

Regional Availability

Europe, Asia Pacific

Special Characteristics

Heat stabilized or stable to heat